Risk Assessment Summary Sheet									Ref 007		
Activity/Workplace; Excavation Works											
Generic Risk Assessment						Risk Assessment after application of Control Measures					
Hazard	Risk	Risk Group	Likelihood	Severity	Risk Rating before controls	CONTROL MEASURES	Responsible Person	Likelihood	Severity	Risk Rating after controls	
Collapse of sides  Striking	Persons in excavations being struck by falling materials. Engulfment Persons falling into excavations Electrocution			5		The presence of buried services must be ascertained from the relevant utilities before work begins. Cable detectors must be used to confirm the results of enquiries from the utilities. Hand tools must only be used when digging within 0.5m of cables.  Any excavations where there is risk of burial or entrapment or a risk of materials falling from a height, the appropriate control must be adhered to. A battered excavation is to be preferred whenever possible as it cannot collapse.  Excavations shall be protected by barriers to prevent workers/public	Line				
underground services  Building or structure collapse due to	Property/ Equipment damage	Employees General	General public 4		20	driving/falling into excavations.  Do not store materials e.g. soil/pipes adjacent to the excavation.  Ensure the side of the excavations do not undermine nearby structures such as walls. Planning and examination of the site before work begins may be necessary.  Any internal combustion engines or other devices producing toxic					
excavations  Plant running into excavations	Personal Injury	,					2	5	10		
Flooding	Drowning										

Revision 1 (2<sup>nd</sup> March 2015)

Page 1 of 1